


Journal of the
National
Academy OF
Forensic
Engineers[®]



<http://www.nafe.org>

ISSN: 2379-3252

Vol. 37 No. 1 December 2020

Forensic Evaluation of Construction Noise and Vibrations Associated with an Urban Drainage Project

By Rune Storesund, DEng, PE, GE (NAFE 474S)

Abstract

This study performed a forensic evaluation of construction noise and ground vibration propagation to surrounding residential and commercial structures as a result of an urban drainage improvement construction project. Noise and vibration data collected during the course of the drainage project was first evaluated for conformance with the project specifications and data collection protocols. Construction equipment utilization logs were used to create a “time history” of daily maximum noise levels, which were contrasted with the maximum allowable per the project specifications. Attenuation relationships were used to delineate ground vibration extents and magnitudes propagating from the source to adjacent receptors (i.e., structures). The forensic engineer (FE) found significant deviations from the required data collection protocols and a high degree of “under-reporting.” Construction-induced noise and ground vibrations were determined to be “substantial factors of harm” to the adjacent structures.

Keywords

Construction dispute, construction noise, construction vibrations, drainage culverts, historic district, loss of use, noise monitoring, structural damage, vibration monitoring, residential impacts, urban construction, forensic engineering

Overview

A lawsuit was filed by residents situated adjacent to a major urban drainage improvement construction project in a historic district against the utility owner (utility) for damages including physical distress and loss of use as a result of the construction activities. The intent of the drainage improvement project was to minimize inundation associated with a 10-year recurrence interval precipitation event. The project entailed the construction of new, below-grade, drainage culverts to temporarily store and more rapidly convey stormwater to discharge points within the larger drainage network. The new culverts were installed primarily beneath a center median of a four-lane residential roadway, which resulted in partial closure and construction activities abutting residential properties.

The FE approach applied to this engagement consisted of the following steps:

- Perform a literature review of the standard of practice for noise and vibration damage;
- Review the project-specific construction bid

package (plans and specifications);

- Review the project-specific construction submittals and requests for information (RFIs);
- Review available construction documentation (daily field reports, photographs, etc.) during the course of the work; and
- Analyze impacts relative to the litigation claims.

For this engagement, the determination of specific structural damage was the responsibility of another expert team. The role of the author, for this case, was to evaluate if the construction-induced construction noise and ground vibrations were “a substantial contributing factor” to the realized damages.

Summary of the State of the Practice — Noise

A number of sources provide insights as to impacts of noise^{1,2,3,4,5,6,7,8,9,10,11,12}. Construction activities, much like highways, generate noise or “unwanted sound”¹². The Federal Transit Administration (FTA) notes that¹²:




Figure 1

Sound energy is a cumulative phenomenon where short-duration loud noises can have similar sound energy as longer duration low noise¹².




Figure 2

Example attenuation due to distance between source and receiver¹².

Noise is generally considered to be unwanted sound. Sound is what we hear when our ears are exposed to small pressure fluctuations in the air. There are many ways in which pressure fluctuations are generated, but typically they are caused by vibrating movement of a solid object. This manual uses the terms “noise” and “sound” interchangeably, since there is no physical difference between them. Noise can be described in terms of three variables: amplitude (loud or soft); frequency (pitch); and time pattern (variability).

The FTA¹² notes that the Sound Exposure Level (SEL) is a quantitative measure of the noise exposure for single noise events. The SEL is a cumulative measure (Figure 1), which means that louder events have a greater SEL than quieter ones, and vents that last longer in time have a greater SEL than shorter ones. FTA notes that “people react to the duration of noise events, judging longer events to be more annoying than shorter ones.” When two or more combinations of sound pressure sources exist, the sound energies are added for an increase in overall sound level. For example, doubling identical sound sources (such as




Figure 3

Community reaction to elevated noise levels¹².




Figure 4

Typical background noise levels¹².

two jackhammers operating at once) result in a 3dB increase. Sound levels decay with distance. Typical attenuation relationships are shown in Figure 2.

Increased noise level has been documented to generate response from exposed communities (Figure 3). Typical background noise levels for urban residential areas is on the order of 60dB (Figure 4). Figure 5 shows typical background noise levels for various conditions. Typical noise ranges for various construction equipment are presented in Figure 6 and Figure 7.

Summary of the State of the Practice — Vibrations

Guidance exists on impacts to structures from construction vibrations^{13,14,15,16,17,18,19,20,21,22}. These reports identify the challenges associated with correlating vibration damage to structural damage. Structure response to ground vibrations depend on many factors, such as the soil

conditions, structure foundation type, structure mass, and structure stiffness¹³. For example, wood and steel are more elastic materials than brick and stone. As a result, wood and steel may be more resistant to ground vibrations¹³. NCHRP 25-25 (Task 72) notes that “[t]he condition of a building and its maintenance are important factors when assessing susceptibility to vibration damage and must be taken into account when setting vibration limits”¹³. In addition, shaking effects of construction-generated ground vibrations can cause ground settlement or shifting that

significantly reduces support provided by the soil, causing damage to the structure(s)^{13,23,24,25,26}.

For continuous vibrations such as vibratory compaction and vibratory pile driving, NCHRP 25-25 Task 72 suggests¹³ the following thresholds for “Peak Particle Velocity” or PPV:

- PPV that exceeds 0.035 in./second is generally considered to be distinctly perceptible;
- PPV of 0.10 in./second would be strongly perceptible and begins to annoy;
- PPV of 0.2 in./second is definitely annoying;
- PPV between 0.4 and 0.6 in./second would be unpleasant.

Sound	dBA
Thunderclap	120
Thunder	110
Stream, water flowing	73
Surf, pounding	70
Wind, breeze through trees	62
Birds, singing	60
Wind, gusty with rustling tree foliage	55
Rainfall, moderate	50
Rainfall, light	40
Rustling leaves	40
Olympic National Forest	40
Mountaintop	35
Wilderness ambient	35
Lake, quiet	30
Meadow, low wind conditions	30
Insects	25
Mountain slope, open	23
Rustling leaves	20
Grand Canyon, remote trail	15
Grand Canyon at night	10
Haleakala volcano crater, no wind	5

Source: Federal Highway Administration 2011.
dBA = A-weighted decibels

Figure 5
Background noise levels for various conditions¹⁰.




Figure 6
Typical sound levels¹³.

Figure 8 shows typical peak particle velocity (PPV) ranges/responses and typical vibration sources. Impact pile driving and vibratory pile driving typically have PPVs on the order of 0.8 to 1.0 in./second at a distance of 25 ft from the source. **Figure 9** shows typical vibration source levels for construction equipment¹³. The Federal Transit Agency¹³ offers a formula to estimate vibration attenuation based on distances greater than 25 ft from the source (**Figure 10**). This simplistic formula is based on distance, the reference PPV, and an adjustment factor based on “competent” soil and “hard” soil. A minimum

	Noise (dBA)			Impact*
	Low	High	Impact*	
Explosives	94	100	*	*
Rock Blast	110	112	*	*
Pneumatic Tools, Jackhammers & Pile Driver	101	110	*	*
Track Hoe	91	106	*	*
Impact Pile Driver	96	106	*	*
Guardrail Installation and Pile Driving	95	105	*	*
Truck Horn	104	104	*	*
Pile Driving	74	103	*	*
Rock Drill and Diesel Generator	80	99	*	*
Rock Drill	85	98	*	*
Dump Truck	82	98	*	*
Rock Drills and Jackhammers	82	97	*	*
Pneumatic Wrenches, Rock Drills	86	97	*	*
Vibratory (Sonic) Pile Driver	95	96	*	*
Diesel Truck	85	96	*	*
Pneumatic Chipper	91	95	*	*
Hydromulcher	87	94	*	*
Clam Shovel	93	93	*	*
Slurry Machine	82	91	*	*
Pneumatic Riveter	91	91	*	*
Circular Saw (hand held)	91	91	*	*
Mounted Impact Hammer Hoe-Ram	85	90	*	*
Concrete Saw	90	90	*	*
Compressor	80	90	*	*
Scraper	85	89	*	*
Paver	80	89	*	*
Large Truck	84	89	*	*
Jackhammer	74	89	*	*
Drill Rig	85	88	*	*
Dozer	84	88	*	*
Crane	85	88	*	*
Pumps, Generators, Compressors	81	87	*	*
Front-end Loader	80	87	*	*
Large Diesel Engine	86	86	*	*
Gradall	85	86	*	*
Chain saws	75	86	*	*
Road Grader	83	85	*	*

	Noise (dBA)			Impact*
	Low	High	Impact*	
Pump	77	80	*	*
Impact Wrench	85	80	*	*
Concrete Truck	81	85	*	*
Concrete Mixer	80	85	*	*
Auger, Drill Rig	85	85	*	*
Flat Bed Truck	84	84	*	*
Backhoe Generator	80	84	*	*
Ground Compactor	82	84	*	*
Concrete Pump	80	82	*	*
Cut slider	81	81	*	*
Roller	74	80	*	*
Horizontal Boring Hydraulic Jack	80	80	*	*
Concrete Vibrator	76	76	*	*
Welder	73	73	*	*
Pickup Truck	85	71	*	*
Yelling	70	78	*	*
Background Sound Level—Forest Habitats	25	44	*	*
Speech (normal)	41	41	*	*

Source: U.S. Fish and Wildlife Service 2006.
* Impact noise = sudden, loud impulsive sound
dBA = A-weighted decibels

Figure 7
Noise ranges for various construction equipment¹⁰.

screening distance of 500 ft is recommended¹³. NCHRP 25-25 notes that “vibration measured at ground level can sometimes be lower than vibrations inside the building due to amplification of vibration caused by resonances in

building floors.”

There is a wide range of opinion on appropriate vibration limits for structures. At one end of the spectrum is a limit of 0.10 in./second (except for ancient ruins/monuments where 0.08 in./second is thought to be appropriate) and at the other end of the spectrum, 0.5 in./second to 2.0 in./second are suggested.




Figure 8

Vibration guidance from NCHRP 25-25 (Task 72)¹³.

Vibration Source Levels for Construction Equipment	
Equipment	PPV at 25 feet
Pile driver (impact)	0.644 to 1.518
Pile drive (sonic/vibratory)	0.170 to 0.734
Vibratory roller	0.210
Hoe ram	0.089
Large bulldozer	0.089
Caisson drilling	0.089
Loaded trucks	0.076
Jackhammer	0.035
Small bulldozer	0.003

Source: Federal Transit Administration 2006.

Figure 9

Table of vibration source levels for typical construction equipment¹³.

$$PPV_{equip} = PPV_{ref} \times (25/D)^n$$

where: PPV (equip) is the peak particle velocity in in/sec of the equipment adjusted for distance
 PPV (ref) is the reference vibration level in in/sec at 25 feet
 D is the distance in feet from the equipment to the receiver
 n is the attenuation exponent
 n = 1.5 for *competent soils*: most sands, sandy clays, silty clays, gravel, silts, weathered rock (can dig with a shovel)
 n = 1.1 for *hard soils*: dense compacted sand, dry consolidated clay, consolidated glacial till, some exposed rock (cannot dig with a shovel, need a pick to break up)

Figure 10

Adjustment equation for estimated vibrations at distances greater than 25 ft¹³.

Project Documentation — Noise

Documentation for the project generated during discovery was reviewed and included: the project plans and specifications; contractor submittals and RFIs; contractor daily field reports; and contractor photos. A review of the project specifications identified requirements for noise. The project specifications required the utility to contract with an independent company to monitor noise levels at the construction easement and notify the contractor of any exceedance instances. “Noise levels shall be limited to 85 decibels measured at the construction easement.” Upon a review of the construction contracts, it became evident that no such independent company had been retained, and no monitoring occurred over the course of the project.

The contractor for the project maintained daily field logs noting the hour of operation of each type of equipment used on the project site each day as well as the number of hours the piece of equipment was in use (Figure 11). Figure 12 presents a summary of the portfolio of equipment used during the course of the construction project.

CONTRACTORS QUALITY CONTROL REPORT (QCR)		REPORT NUMBER
DAILY LOG OF CONSTRUCTION		310 Page 2 of 2
DATE		27 Jul 2012 - Friday
PROJECT		[REDACTED]
CONTRACT NUMBER		[REDACTED]
QA/QC DEFICIENCY (Describe QC Deficiency items issued, Report QC and QA Deficiency items corrected)		
No QC Deficiency items were issued today		
No Deficiency items were corrected today		
CONTRACTORS ON SITE (Report first and/or last day contractors were on site)		
No contractors had their first or last day on site today		
LABOR HOURS		
The following labor hours were Reported today:		
Employer	Labor Classification	Number of Employees Hours Worked
[REDACTED]	FOREMAN	5.0 40.0
[REDACTED]	LABORERS	14.0 80.0
[REDACTED]	OPERATING ENGINEER	6.0 38.0
[REDACTED]	QC PERSONNEL	1.0 8.0
[REDACTED]	SAFETY ENGINEER - ON SITE	1.0 8.0
[REDACTED]	SUPERINTENDENT	1.0 8.0
[REDACTED]	SURVEYOR	2.0 16.0
[REDACTED]	WELDER	2.0 14.0
Total hours worked to date: 7,099.0		Total 32.0 212.0
EQUIPMENT HOURS		
The following equipment hours were Reported today:		
Serial Number	Description	Idle Hours Operating Hours
104.137	Air Compressor	0.00 8.00
191.309	Deere 310 puddle jumper	0.00 8.00
191.357	Deere 310 puddle jumper	0.00 8.00
191.428	Puddle Jumper	0.00 8.00
192.032	John Deere 124	0.00 8.00
192.048	CAT 312 Puddle jumper	0.00 8.00
192.056	CAT 312 Excavator	0.00 8.00
251.113	Deere Dozer	0.00 8.00
820313	Street Sweeper	0.00 8.00
191112011	Cui 420 Pj Puddle Jumper	0.00 8.00
Total operating hours to date: 4,032.00		Total 0.00 60.00

Figure 11

Example contractor daily field report showing equipment used and number of hours. Source: Discovery Docs.

Equipment Description	Serial No.	Noise Type	Equipment Description	Serial No.	Noise Type
185CFM Air Compressor	104.118	1	JD Rubber Tire Backhoe	191.428	2
185CFM Air Compressor	104.137	1	Jet Truck	425.005	2
210G LC John Deere Trackhoe	193.148	1	John Deere 35D Mini-Excavator	JD35D	2
Air Compressor	104.137	1	John Deere 50C 2TS Excavator	192.036	2
Air Compressor	104.154	1	John Deere 134	192.032	2
Air Compressor	108.760	1	John Deere Backhoe 135D	192.057	2
Air Hammer	691.056	1	John Deere Dozer	251.119	2
American 5299A Crane	224.016	1	John Deere Excavator	193.115	2
American 5300 Crane	225.009	1	John Deere Excavator - 200C	193.118	2
Blue Iron Silent Piler	Bluelron01	1	John Deere 310SK Rubber tire	191.460	2
CAT 312C Trackhoe	192.046	1	John Deere Rubber Tire Backhoe 310 SJ	191.409	2
CAT 329E Trackhoe	193.138	1	John Deere 310 SK Rubber Tire Backhoe	191.451	2
HP 915 Air Compressor	109.905	1	John Deere Trackhoe 135c RTS	192.041	2
IR 185CFM Air Compressor	104.169	1	John Deere Trackhoe 135c RTS	192.043	2
IR 185CFM Air Compressor	104.182	1	Kobelco Crane 85 ton	CK850	2
IR 185CFM Air Compressor	104.201	1	Komatsu D21P Dozer	250.100	2
Vibro Hammer	700.43	1	Komatsu Bull Dozer	250.101	2
Wood Chipper 1	Bayou Tree 5	1	Kubota Generator	471.126	2
Wood Chipper 2	Bayou Tree 6	1	Kubota SQ-33 Generator	471.130	2
250T Liebherr	B&G 01	2	Link-Belt 50T	224.027	2
315 Excavator	192.019	2	Link-Belt 50T	224.026	2
6" Hydraulic Pump	422.042	2	Manitowoc Crane 3900	226.261	2
6" Hydraulic Pump	422.043	2	Manitowoc W 4000	227.387	2
6" Hydraulic Pump	422.048	2	Offroad Forklift	569076	2
6" Hydraulic Pump	422.049	2	Offroad Forklift	RSC0001	2
8" Hydraulic Pump	422.053	2	Pump Truck (Schwing)		2
American Auger - Tri-State	Tri-State1	2	Pump Truck (Putzmeister)		2
American HC 80 TERE X	225.083	2	Pump Truck	511.023	2
American HC 110 TEREX	R226514002	2	Pump	0.00000	2
Asphalt Milling Machine	482.012	2	Roller	446.030	2
Asphalt/MTV	451.016	2	Roller	466.031	2
Asphalt Paver	451.030	2	Roller	446.035	2
Asphalt Shuttle Buggy	451.028	2	Rubber Tire Backhoe	191.440	2
Bobcat	Bayou Tree 7	2	Rubber Tire Backhoe	191.434	2
Bobcat BXT	192.047	2	Rubber Tire Backhoe	191.454	2
Bobcat Cold Planer	482.011	2	Rubber Tire Backhoe	R191114002	2
BobCat E35i	10276274	2	Street Sweeper	431.030	2
Bobcat Skidsteer	371.015	2	Street Sweeper	431.031	2
CAT 312 Excavator	192.046	2	Street Sweeper	431.032	2
CAT 312 Excavator	192.049	2	Street Sweeper	431.033	2
CAT 312 Excavator	192.056	2	Street Sweeper	829313	2
CAT 314 Excavator	R192214002	2	SunBelt 18" Pump	Sun Belt	2
CAT 325D Excavator	193.129	2	SunBelt 18" Pump	SunBelt1	2
CAT 325 Excavator	193.130	2	SunBelt 18" Pump	SunBelt2	2
CAT 329 Excavator	LA Rental 00001	2	SunBelt 18" Pump	SunBelt3	2
CAT 329E Excavator	PLW135	2	Takeuchi Mini-Excavator TB016	UR849477	2
CAT 345B Excavator	195.035	2	Takeuchi Mini Excavator	United Rental	2
CAT 345clong stick excavator	195.041	2	Terex HC80	225.087	2
CAT 312 Puddle jumper	192.048	2	Volvo Backhoe Long Stck	EC 300DLR	2
CAT 420F Puddle Jumper	LA Rent 01	2	Volvo Long Stick Excavator	EC300DLR-2	2
CAT 420PJ Puddle Jumper	R191112011	2	Volvo Roller	Volvo1	2
CAT D4 Dozer	251.127	2	Volvo Track hoe	EC300D	2
CAT Excavator	363.040	2	XP-185 Air Compressor	104.161	2
CAT CB-334E Roller	446.024	2	8-15 Ton Asphalt Roller	446.029	3
CAT Roller CS-433E	445.015	2	10 Ton Fork Lift	rented-000	3
CAT Front-End Loader	520.029	2	115' Fixed Leads	705.328	3
Caterpillar Asphalt Paver	451.029	2	Bucket Truck	Bayou Tree 1	3
Caterpillar Asphalt Paver	451.030	2	Bucket Truck	Bayou Tree 2	3
Caterpillar Excavator	R193115006	2	CAT Rubber Tire Exc	191.493	3
Caterpillar Loader/Backhoe	191.445	2	Caterpillar Fork Carriage	520.470	3
Caterpillar Ldr/Bkh Forks	520.035	2	Cherry Picker	HTC0080-01	3
Deere 310 Puddle Jumper	191.309	2	F350	Bayou Tree 8	3
Deere 310 Puddle Jumper	191.357	2	F650	Bayou Tree 3	3
Deere Dozer	251.113	2	F650	Bayou Tree 4	3
EC35C Mini Excavator	58332-189	2	Forklift JLG	569076	3
Excavator	192.069	2	Fuel Tank 500-550 Gal Skid	711.040	3
Generator	R471315001	2	JLG Manlift 6005 402116	263.012	3
Grove RT 500C	221.052	2	J.L.G. Sky Trak forklift	521.048	3
J-Star JD Puddle Jumper	JSTAR0001	2	Lincoln Welding Machine	163.111	3
JD 50D Mini Excavator	192.061	2	Link Belt Cherry Picker - 40/60Ton	224.06	3
JD 270 Excavator	192.039	2	Linkbelt Cherry Picker	224.261	3
JD 270 Excavator	193.132	2	Linkbelt RTC 8050 50 Ton Cherry Picker	224.026	3
JD 270LC Track Hoe	193.120	2	M-Jack MJ-40 Travelift	R240014001	3
JD 450D Excavator	195.040	2	NES Manlift 860SJ	N5838	3
JD 275 Long Stck	193.131	2	Peterbilt Tack Truck	502.113	3
JD 550 Dozer	251.110	2	RTC 8050 Link Belt Series II Cherry Picker	224.027	3
JD 550 Dozer	251.124	2	Service Truck	506.115	3
JD Dozer	251.102	2	Swinging Leads 26"X115'	705.001	3
JD Dozer	251.120	2	Tool Trailers/Skid	631.180	3
JD Puddle Jumper	191.426	2	Tool Trailers/Skid	631.184	3
JD Puddle Jumper	191.451	2	Tool Trailers/Skid	631.208	3
JD Puddle Jumper 310SK	191.457	2	Tool Trailers/Wheeled	631.253	3
Puddle Jumper	191.358	2	Water/Service Truck	502.116	3
Puddle Jumper	191.428	2	Welding Machine	164.421	3

Figure 12
Summary of construction equipment used during the course of the construction project. Source: Author.

19. VIBRATION MONITORING

Vibrations due to all construction activities including driving sheet piles will be monitored. The Contractor shall perform the work in a manner which will limit vibrations at the structure nearest to the work being performed to a maximum of 0.25 inch per second. Vibrations will be monitored by others at all structures, including buildings and pools. The Contractor will be informed when the vibrations from his operation have exceeded the 0.25 inch per second limit and the Contractor shall take immediate action to reduce the vibrations to acceptable limits. The Contractor shall give the [redacted] notice at least 15 days prior to beginning vibration-inducing construction operations, and shall coordinate the daily location of these operations with the government personnel at least 48-hours prior. The Contractor shall also be responsible for contacting the vibration monitoring firm to schedule the necessary vibration monitoring personnel.

Figure 13

Excerpt from the project specifications addressing vibration monitoring. Source: Discovery Docs.

Project Documentation — Vibrations

Documentation for the project generated during discovery was reviewed and included: the project plans and specifications; contractor submittals and RFIs; contractor daily field reports; and contractor photos. A review of the project specifications identified requirements for construction-induced vibrations as well as the vibration monitoring requirements. The project specifications (Figure 13) required the utility to contract with an independent company to monitor vibrations “at all structures, including buildings and pools.”

A consulting engineering firm (vibration consultant) was retained by the utility. The vibration consultant used two alpha-seismite digital seismographs. These instruments were manually monitored in lieu of more rapid and reliable automated reporting arrays.

The author notes that for a project as extensive as this, automated arrays provide far superior data collection and alert systems as they can be installed at the beginning of the project and used as a basis for interpolating across the project site. Empirically based 2D propagation maps can be generated to better manage construction-induced ground vibrations and overcome manually placed monitors too far from the construction work in order to characterize vibrations at the “structure nearest the work being performed,” as required by the project specifications.

Reports were prepared daily by the on-site vibration consultant personnel that listed the maximum PPV values recorded, a general description of the monitoring location (including a sketch by the vibration monitoring technician), and notations of general construction activities in the vicinity of the vibration monitoring.

Noise Baseline Conditions

While the noise literature provides some guidance on noise levels, data was collected during the time forensic engineering analyses and reporting were underway by a

specialty sound consultant. This work occurred after completion of the project, so results were inferred to be representative of pre-project conditions. Sound measurement devices were placed at select locations along the historic construction right of way (Figure 14). (Note: The construction right of way per the project drawings essentially terminated at the residential property lines along the sidewalk).

Continuous sound recordings were made over the course of one week across the former project site. An overlay, based on time period, is presented in Figure 15. Each color plot represents a different location along the construction route. Spikes in the time histories are typically the result of emergency response vehicles (police, fire, ambulance). The low bound ambient noise level during the course of the “work day” (8 a.m. to 5 p.m.) is approximately 55 dB and a high of approximately 67 dB. This range is consistent with the published literature of anticipated noise levels for an “urban residential area.”

The measured ambient background noise closely matched the ranges reported in the published literature



Figure 14

Example configuration of a sound monitoring location set up at the historic construction right of way. Source: Sound consultant.




Figure 15

Representative ambient background sound levels along the construction route limits. Source: Sound consultant.

(Figure 16). The construction noise levels in excess of 85 dB result in a noise difference of 20 to 30 dB from baseline level at 60 dB, which, according to the published literature of community reaction (Figure 3), predicts strong reaction from the community. Community complaints were one of the plaintiff’s claims against the utility. A-weighting was used, which is a standardized filter used to alter the sensitivity of a sound level meter with respect to frequency so that the instrument is less sensitive at low and high frequencies where the human ear is less sensitive — also written as dBA.

Construction Noise Analysis

The forensic noise analysis consisted of reviewing the inventory of equipment listed on each of the contractor’s daily field report (Figure 11). Each piece of equipment was classified into one of three noise categories, based on the published literature identifying typical noise levels based on general equipment type:

- Red – more than likely in excess of 85 dB.
- Yellow – likely in the range of 85 dB.
- Green – likely less than 85 dB.

The maximum noise producing equipment on the project for each day was summarized and plotted on a calendar (Figure 17) to show the court the chronic and routine exceedance of the noise threshold (85 dB) at the construction easement.

A major challenge was documenting the specific




Figure 16

Comparison of construction noise levels relative to ambient background levels¹⁷.




Figure 17

Summary of daily maximum noise level based on utilized contractor equipment over the course of the project. Source: Author.

locations of the equipment for each day to more precisely map the “noise zone” associated with the utilized equipment, but the documentation made available was insufficient to accomplish this in a reasonable manner. The contractor did provide a phased construction schedule for the project as a whole. This over-arching schedule was used to infer the general regions impacted by the equipment noise.

The work varied spatially across the work area throughout the day and throughout the project duration. The width of the work limits was generally on the order of 85 ft. The typical distance of the residential structures and




Figure 18

Typical configuration showing construction easement zone and proximity of adjacent residential structures. Source: Author.

the construction easement (**Figure 18**) was on the order of 25 ft.

Counter claims were made that the majority of the residents were away during the work day, and, as a result, were not inconvenienced by these exceedances. While an intriguing argument, it has no merit due to the fact that: (1) the project specifications clearly limit the maximum noise level to 85 dB at the construction easement irrespective of the time of day; (2) no effort was made by either the utility or the contractor to survey the adjacent residents if they were bothered by the noise; and (3) repeated complaints were made by the residents to a project complaint line regarding the construction noise and disruption of their use and enjoyment during the construction project.

It was also argued that the noise level inside the residential structures was likely less than 85 dB due to attenuation through the structure's framing. However, this argument also had no merit due to the fact that the project specifications restricted the noise to a maximum of 85 dB at the construction easement, not at the residential structure or inside the residential structure.

Courtroom Demonstrative — Noise

A courtroom demonstrative was developed to convey to the court the concepts of amplitude, frequency, and time pattern associated with noise, where¹⁷:

Amplitude — Loudness of a sound as a result of differences between the extremes of an oscillating sound.

Decibel — The standard unit of measurement for sound pressure level and vibration level. Technically, a decibel is the unit of level that denotes the ratio between two quantities that are proportional to power; the number of decibels is 10 times the logarithm of this ratio, also written as dB.

Frequency — The number of times that a periodically occurring quantity repeats itself in a specified period. With reference to noise and vibration signals, the number of cycles per second.

Time Pattern — Variation of noise over time.

The most important element of the demonstrative was communicating the relationship between amplitude and reported dB level. Because an increase of 1 dB is a tenfold increase in sound pressure levels, illustrating the sound levels was important to ensure there was an appreciation

between a sound at 85 dB and 95 dB.

The demonstrative was configured so that speakers were oriented toward the judge, and sound levels were calibrated to reach the intended sound level (dB) at an off-set distance of 20 ft (distance between the speakers and the judge). Sound meters were positioned at the judge's location to verify the intended dB level was achieved.

A portfolio of sounds was recorded from construction activities. Some recordings were based on current work in remaining areas of work for the drainage improvement project. Other recordings were based on video captured by residents during the course of the work. The recordings included (**Figure 19**):

- Ambient traffic noise (55 dBA & 65 dBA)
- Concrete breaker (85 dBA)
- Concrete saw (90 dBA)
- Roller compactor (95 dBA)
- Pile driver (100 dBA to 115 dBA)

While earplugs were made available to safely experience the full portfolio of recorded sounds, the court requested the demonstrative terminate upon reaching the 90 dBA example as the noise levels became very disagreeable.

Construction Vibration Analysis

Over the course of the construction project, 763 vibration reports were reviewed and tabulated. Of those reports, approximately 44% had daily maximum PPV values equal to or greater than 0.25 in./second (**Figure 20** and **Figure 21**) throughout the project area.

Figure 21 presents a spatial plot of setup locations of the vibration monitoring equipment and scaled circles are associated with each monitor location with a max PPV greater or equal to 0.25 in. per second. The recordings are representative of the ground vibrations observed at the unique vibration monitor location from all surrounding vibration sources.

Vibrations attenuate over distance. While the project specifications require monitoring "at the closest structure," the vibration monitors were frequently situated at more distant structures, with no monitoring at the "closest




Figure 19

Overview of sounds included in the courtroom demonstrative. Source: Sound consultant.

structure” as required by the project specification.

The reported ground vibrations do not represent the maximum construction-induced vibration “the nearest structure” would experience. **Figure 22** shows a photo taken by the contractor during the course of the work where the vibration monitor was not situated in a position to represent construction-induced ground vibrations ‘at the nearest structure. Additionally, numerous field reports note work occurring at significant distances from the

vibration monitor, as shown in **Figure 23**.

These factors lead to “under-reporting,” where the reported values do not satisfy the project specifications, which require reporting values at the “nearest structure,” rather than “at the monitoring device.”

The PPVref value was back-calculated to establish the ground vibration magnitude at a distance of 25 ft. Thus, if the vibration monitor was located more than 25 ft from the




Figure 20

Vibration monitoring days where the maximum PPV exceeded the allowable threshold. Source: Author.




Figure 21

Plot of recorded maximum daily PPV values (in./second). Source: Author.

source, the equivalent PPV at 25 had to be back-calculated. Following establishment of the PPV_{ref}, vibration magnitudes based on distance were calculated and reported as PPV_{equip}. Results are illustrated in **Figure 27** through **Figure 30**.

The dashed blue line in **Figure 27** through **Figure 30**



Figure 22

Example where vibration monitor was not situated at a location representative of vibrations experienced “at the nearest structure.” Source: Discovery Docs.

delineate the construction easement. As can be seen in the attenuation results, construction-induced ground vibrations exceeding the project threshold of 0.25 in. per second extend well beyond the project construction easement. As a result, the construction-induced ground vibrations were determined to be “substantial factors of harm” to the adjacent structures.

Conclusion

A lawsuit was filed by residents situated adjacent to a major urban drainage improvement construction project in a historic district against the utility owner (utility) for damages, including physical distress and loss of use as a result of the construction activities. This study performed

VIBRATION MONITORING REPORT Page 8 of 9

PROJECT NO.	21689	DATE	3/28/17	
TECHNICIAN	Jonathan M. Lewis	PROJECT LOCATION	California Avenue Phase 1 (SEA 2nd)	
EQUIPMENT	White Sennheiser # 208	MONITOR NO.	1 #1	
TIME	LOCATION	DISTANCE FROM SOURCE	MAXIMUM PPV (IN./SEC)	DESCRIPTION AND COMMENTS
07:00 - 07:30	#1	15' - 25'	0.1 (g)	Site: breaking concrete in slab on grade
07:30 - 08:00	#1	20' - 20'	0.4 (g)	Site: breaking concrete in slab on grade
08:00 - 08:30	#1	25' - 45'	0.3 (g)	Site: breaking concrete
08:30 - 09:00	#1	25' - 25'	0.25 (g)	Site: breaking concrete
09:00 - 09:30	#1	25' - 25'	0.25 (g)	Site: breaking concrete
09:30 - 10:00	#1	25' - 25'	0.25 (g)	Site: breaking concrete
10:00 - 10:30	#1	25' - 25'	0.25 (g)	Site: breaking concrete
10:30 - 11:00	#1	25' - 25'	0.25 (g)	Site: breaking concrete
11:00 - 11:30	#1	25' - 25'	0.25 (g)	Site: breaking concrete
11:30 - 12:00	#1	25' - 25'	0.25 (g)	Site: breaking concrete




Figure 25

Calculation of vibration attenuation from January 31, 2014. Source: Discovery Docs.

VIBRATION MONITORING REPORT Page 1 of 6

PROJECT NO.	21689	DATE	February 3 / 28 / 17	
TECHNICIAN	Jonathan M. Lewis	PROJECT LOCATION	California Avenue Phase 1 (SEA 2nd)	
EQUIPMENT	White Sennheiser # 208	MONITOR NO.	1 #1	
High PPV at 50 ft				
TIME	LOCATION	DISTANCE FROM SOURCE	MAXIMUM PPV (IN./SEC)	DESCRIPTION AND COMMENTS
07:00 - 07:30	#1	50'	(A) .78	Komatsu excavator moving construction materials
07:30 - 08:00	#1	50'	(B) .10	Komatsu excavator moving construction materials
08:30 - 09:00	#1	200' to 240'	negligible	Komatsu excavator grading and excavating work area
09:00 - 09:30	#1	200' to 240'	negligible	site work / low activity
09:30 - 10:00	#1	200' to 240'	negligible	Komatsu excavator grading and excavating work area
10:00 - 10:30	#1	200' to 240'	negligible	site work / low activity
10:30 - 11:00	#1	200' to 240'	negligible	site work / low activity
11:00 - 11:30	#1	200' to 240'	negligible	site work / low activity
11:30 - 12:00	#1	200' to 240'	negligible	site work / low activity

Low PPV at >200 ft

VIBRATION SOURCE: Komatsu excavator / Komatsu bulldozer / backhoe loader / bottom line Jackhammer / Volvo forklift

SCALE: 0.00 to 1.2 3dB

REMARKS: Location #1 is 25' east of Montecello Ave. 176' South of Nelson St. 200' to 240' North of the work area. Work was also performed 50' east of location #1 while work was being performed in this area. The work resulted above .85 dBm from with the Army Corp was notified.

Figure 23

Example daily vibration monitoring report. Source: Discovery Docs; notes by author.

Location (I)			Location (J)			Location (K)		
PPV _{ref}	D	PPV _{equip}	PPV _{ref}	D	PPV _{equip}	PPV _{ref}	D	PPV _{equip}
0.66	25	0.66	1.26	60	0.34	0.93	60	0.25
0.66	5	7.38	1.26	5	14.13	0.93	5	10.39
0.66	30	0.50	1.26	30	0.96	0.93	30	0.71
0.66	35	0.40	1.26	35	0.76	0.93	35	0.56
0.66	40	0.33	1.26	40	0.62	0.93	40	0.46
0.66	45	0.27	1.26	45	0.52	0.93	45	0.38
0.66	50	0.23	1.26	50	0.45	0.93	50	0.33
0.66	60	0.18	1.26	60	0.34	0.93	60	0.25
0.66	70	0.14	1.26	70	0.27	0.93	70	0.20
0.66	80	0.12	1.26	80	0.22	0.93	80	0.16
0.66	90	0.10	1.26	90	0.19	0.93	90	0.14
0.66	100	0.08	1.26	100	0.16	0.93	100	0.12

Dist to 0.25 ips: 48 74 60

Figure 24

Construction-induced ground vibration attenuation calculation. Source: Author.



Figure 26

Location of construction-induced ground vibration attenuation example with three monitor setup locations and three exceedance events. Source: Author.




Figure 27

Attenuation of Event "I" with project plan overlay showing event origin relative to planned work. Source: Author.




Figure 30

Overlay of attenuation of all three events (I, J, and K). Source: Author.




Figure 28

Attenuation of Event "J" with project plan overlay showing event origin relative to planned work. Source: Author.




Figure 29

Attenuation of Event "K" with project plan overlay showing event origin relative to planned work. Source: Author.

an FE of construction-induced noise and ground vibrations impacting residents near the construction activities.

Noise data collected during the course of the drainage project were used to create a "time history" of daily maximum noise levels. These maximum noise levels were contrasted with the maximum allowable per the project specifications. The FE found significant deviations from the required data collection protocols and routine violation of the maximum allowable thresholds specified for the project.

Attenuation relationships were used to delineate ground vibration extents and magnitudes propagating from the source to adjacent receptors (i.e., structures). The FE found significant deviations from the required data collection protocols and a high degree of "under-reporting." Construction-induced ground vibrations were determined to be "substantial factors of harm" to the adjacent structures.

The case was tried in state court via bench trial. The court's decision mirrored the findings of the forensic analyses.

References

1. E. P. Agency, "Information on Levels of Environmental Noise Requisite to Protect Public Health and Welfare with an Adequate Margin of Safety; Report No. 550/9-74-004," Washington DC, 1974.
2. F. I. C. o. U. Noise, "Guidelines for Considering Noise in Land Use Planning and Control; a joint publication of the Environmental Protection Agency, the Department of Transportation, the

- Department of Housing and Urban Development, the Department of Defense, and the Veterans,” Washington DC, 1980.
3. D. o. H. a. U. Development, “Environmental Criteria and Standards of the Department of Housing and Urban Development, 24 Code of Federal Regulations Part 51; 44 Federal Register 40861,” Washington DC, 1979.
 4. A. N. S. Institute, “American National Standard: Compatible Land Use with Respect to Noise, Standard S3.23-1980,” New York, 1980.
 5. A. N. S. Institute, “American National Standard: Quantities and Procedures for Description and Measurement of Environmental Sound – Part 5. Sound Level Descriptors for Determination of Compatible Land Use, Standard S12.9-1998/Part 5,” New York, 1998.
 6. T. J. Schultz, “Noise Rating Criteria for Elevated Rapid Transit Structures, U.S. Department of Transportation Report No. UM-TA-MA-06-0099-79-3,” U.S. Department of Transportation, Washington DC, 1979.
 7. T. J. Schultz, “Synthesis of Social Surveys on Noise Annoyance,” *Journal of the Acoustical Society of America*, vol. 63, no. 8, August 1978.
 8. S. Fidell, D. S. Barber and T. J. Schultz, “Updating a Dosage-Effect Relationship for the Prevalence of Annoyance Due to General Transportation Noise,” *Journal of the Acoustical Society of America*, vol. 89, no. 1, 1991.
 9. S. Fidell, “The Schultz Curve 25-years Later: A Research Perspective,” *Journal of the Acoustical Society of America*, vol. 114, no. 6, 2003.
 10. E. W. West, “Technical Guidance for Assessment and Mitigation of the Effects of Traffic Noise and Road Construction Noise on Bats,” Caltrans, Sacramento, 2016.
 11. U. D. o. T. (USDOT), “Highway Traffic Noise Analyses and Abatement,” U.S. Department of Transportation, Federal Highway Administration, Office of Environment and Planning, Noise and Air Quality Branch, Washington DC, 2011.
 12. Federal Transit Administration, “Transit Noise and Vibration Impact Assessment.” Prepared by C. E. Hanson, D. A. Towers, and L. D. Meister, Burlington, MA. Prepared for Office of Planning and Environment, Washington, DC., 2006.
 13. Wilson, Ihrig & Associates, Inc., ICF International and Simpson, Gumpertz & Heger, Inc., “NCHRP 25-25/Task 72, Current Practices to Address Construction Vibration and Potential Effects to Historic Buildings Adjacent to Transportation Projects,” 2012.
 14. American Association of State Highway and Transport, “Standard Recommended Practice for Evaluation of Transportation Related Earthborne Vibrations, AASHTO R8-96,” Washington, DC, 2004.
 15. California Department of Transportation, “Transportation- and Construction-Induced Vibration Guidance Manual, Prepared by Jones & Stokes, Sacramento, CA.,” 2004.
 16. Esrig, M. I., and A. J. Ciancia., “The Avoidance of Damage to Historic Structures Resulting from Adjacent Construction,” *American Society of Civil Engineers*, New York, NY, 1981.
 17. Federal Transit Administration, “Transit Noise and Vibration Impact Assessment.” Prepared by C. E. Hanson, D. A. Towers, and L. D. Meister, Burlington, MA. Prepared for Office of Planning and Environment, Washington, DC., 2006.
 18. International Organization for Standardization, “Mechanical Vibration and Shock; Vibration of Buildings: Guidelines for the Measurement of Vibrations and Evaluation of their Effects on Buildings.” Second edition. ISO 4866-2010., 2010.
 19. Kelley, P. L., S. J. DelloRusso, and C. J. Russo., “Building Response to Adjacent Excavation and Construction.” Pp. 80-97., Boston, 1998.
 20. Konon, W. and J. R. Schuring., “Vibration Criteria for Historic and Sensitive Older Buildings.,” vol. 111, no. 3.
 21. Whiffin, A. C., and D. R. Leonard., “A Survey of Traffic-induced Vibrations. Road Research

Laboratory Report LR418.," 1971

22. Caltrans, "Transportation and Construction Vibration Guidance Manual; CT-HWANP-RT-13-069.25.3," Sacramento, 2013.
23. J. E. Bowles, Foundation Analysis and Design, Fourth Edition, New York: McGraw-Hill Book Company, 1988.
24. S. L. Kramer, Geotechnical Earthquake Engineering, Upper Saddle River: Prentice-Hall International, 1996.
25. USACE, USACE Engineering Manual 1110-1-1904, Washington, DC: USACE, 1990.
26. H.-Y. Fang, Foundation Engineering Handbook, 2nd Edition, New York City: Chapman & Hall, Inc., 2004.

